


15-165-20181-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rush County, Sec. 35 Twp. 16S Rge. (X) 20 (W)
Location as "NE/CNWKSW" or footage from lines. SE SE SE
Lease Owner John C. Graves, et al
Lease Name Derr Well No. 1
Office Address 505 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 30, 19 68
Application for plugging filed September 30, 19 68
Application for plugging approved September 30, 19 68
Plugging commenced September 30, 19 68
Plugging completed September 30, 19 68
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3950 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	228'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 540 feet. Followed by wooden plug and 1/2 sack hulls. Placed 70 sacks cement onto hulls. Mudded up with heavy mud to 210 feet followed by wooden plug, 1/2 sack hulls and 20 sacks cement. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/2 sack hulls and 10 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Graves Drilling Co., Inc.
Address 505 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
John C. Graves (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves
505 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of October, 19 68

My commission expires May 9, 1971


Betty Brandt
Betty Brandt Notary Public.

R O T A R Y D R I L L E R S ' L O G

OPERATOR: John C. Graves, et al DRILLING COMMENCED: September 23, 1968
505 Union Center
Wichita, Kansas 67202

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: September 30, 1968
505 Union Center
Wichita, Kansas 67202

CASING RECORD: 11 Jts. 228' 8-5/8" LOCATION: Derr No. 1
cemented with 185 sacks SE SE SE
Section 35-16S-20W
Rush County, Kansas



0 - 229	Sod, clay & post rock
229 - 445	Shale & shells
445 - 775	Shale & red bed
775 - 995	Sand
995 - 1363	Anhydrite
1363 - 1645	Red bed & shale
1645 - 1910	Shale & lime
1910 - 2821	Lime & shale
2821 - 3135	Shale & lime
3135 - 3435	Lime
3435 - 3440	Shale
3440 - 3500	Lime & shale
3500 - 3711	Lime
3711 - 3807	Lime & shale
3807 - 3845	Lime
3845 - 3865	Lime & shale
3865 - 3950	Lime
3950	Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1968
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John C. Graves
President

STATE OF KANSAS)
) ss:
SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, this 7th of October, 1968.

My commission expires May 9, 1971

Betty Brandt
Betty Brandt Notary Public