

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

	34		

Locate well correctly on above
Section Plat

Rush County, Sec. 34 Twp. 16S Rge. (E) 20 (W)
Location as "NE/CNW/SE/SW" or footage from lines NE NE NE
Lease Owner Rains & Williamson Oil Co., Inc.
Lease Name JENNINGS Well No. 1
Office Address 1425 Wichita Plaza - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8-21 19 68
Application for plugging filed 8-21 19 68
Application for plugging approved 8-21 19 68
Plugging commenced 8-21 19 68
Plugging completed 4:30 A.M. 8-21 19 68
Reason for abandonment of well or producing formation No oil or gas found
in commercial quantities.
If a producing well is abandoned, date of last production -- 19 --
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas
Producing formation None Depth to top -- Bottom -- Total Depth of Well 3955 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	266'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pumped down surface pipe with plug ahead, 130 sacks
50-50 Pozmix, 6% gel, with 200# hulls ahead. Plugging
completed 4:30 A.M. 8-21-68.

RECEIVED
STATE CORPORATION COMMISSION
AUG 23 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Rains & Williamson Oil Co., Inc.
Address as shown above

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wilson Rains, ~~employee of owner~~ or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains Wilson Rains
1425 Wichita Plaza - Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22 day of August, 19 68
Sherry Gish
My commission expires 6-30-71 Sherry Gish Notary Public.

ROTARY DRILLING LOG

Operator: Rains & Williamson
Oil Co., Inc.
JENNINGS #1
C NE NE NE Sec. 34-16S-20W
Rush County, Kansas

Contractor: Rains & Williamson
Oil Co., Inc.

Commenced: 8-12-68

Completed: 8-21-68

Remarks: Set 8-5/8" surface
casing at 266' w/
155 sx. GL-3, 2% gel.

Formations

Surface Soil	20'
Shale	800'
Sand	1020'
Red Bed and Shale	1357'
Anhydrite	1392'
Shale	2025'
Shale and Shells	2120'
Lime and Shale	2250'
Lime	2520'
Lime and Shale	2865'
Shale and Lime	3320'
Lime and Shale	3535'
Lime	3955'

Rotary Total Depth (D & A) 3955'


RECEIVED
STATE CORPORATION COMMISSION
AUG 23 1968
CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is true
and correct to the best of our
knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.


Wilson Rains

Subscribed and sworn to before me, a Notary Public in and for the State of
Kansas, County of Sedgwick, this 22 day of August, 1968.


Sherry Gish Notary Public

My Commission Expires:
June 30, 1971

