

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-165-21,470-0000

LEASE NAME Weltmer

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER #1-35

1,350 Ft. from S Section Line

2,980 Ft. from E Section Line

SEC. 35 TWP. 16 RGE. 10 or (W)

COUNTY Rush

Date Well Completed 5/23/89

Plugging Commenced 4/2/91

Plugging Completed 4/4/91

LEASE OPERATOR Balcron Oil

ADDRESS P.O. Box 21017 Billings, MT 59104

PHONE#(406) 259-7860 OPERATORS LICENS NO. 03701

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on October 4, 1990 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well loc. attached? _____

Producing Formation Arbuckle Depth to Top 3,888' Bottom T.D. 3,890'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
 STATE CORPORATION COMMISSION

Formation	Content	From sfc	To	Size	Put in	Pulled out
Arbuckle	oil		317'	8-5/8"	371'	0'
		317'	3888	5-1/2"	3888'	1,550'

MAY 16 1991

CONSERVATION DIVISION
 Wichita Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
6 bags of sand on bottom with dump bailer. 4 sx cement with dump bailer on top of sand at bottom. Shot off 5-1/2" casing at 1,550' and pulled pipe. Fill hole with 225 sx of cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Cheyenne Well Service License No. 6454

Address P.O. Box 384 Ness City, KS 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Operator

STATE OF Montana COUNTY OF Yellowstone, ss.

James Alan Townsend (Employee of Operator) or ~~(Operator)~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) James Alan Townsend

P.O. Box 21017

Billings, MT 59104

SUBSCRIBED AND SWORN TO before me this 13th day of May, 1991

[Signature]
 Notary Public

My Commission Expires: January 25, 1994

