

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-165-21,608-0000

LEASE NAME Walker

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1-26

3630 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 26 TWP. 16 RGE. 20 (X) or (W)

COUNTY Rush

Date Well Completed 05-01-92

Plugging Commenced 05-01-92

Plugging Completed 05-02-92

LEASE OPERATOR Brito Oil Company, Inc.

ADDRESS 200 E. First, Suite 208 Wichita, KS 67202

PHONE# (316) 263-8787 OPERATORS LICENSE NO. 4629

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 04-30-92 (date)

by Case Morris (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3880'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ foot each set.

Bottom Plug: @ 1400' w/50 sacks cement thru drill pipe
 Next Plug: @ 700' w/80 " " " " " 15 sacks in Rathole
 Next Plug: @ 260' w/50 " " " " "
 Top Plug: @ 40' w/10 " " " " "

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: BRITO OIL COMPANY, INC

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

RAUL F. BRITO (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) _____

(Address) _____

SUBSCRIBED AND SWORN TO before me this _____ day of _____

Kenneth S. White
Notary Public

My Commission Expires: _____



RECEIVED
STATE CORPORATION COMMISSION
MAY 20 1992
CONSERVATION DIVISION
Wichita, Kansas

ORIGINAL K.S. 165-21608-0000

DRILLER'S WELL LOG

DATE COMMENCED: April 26, 1992
DATE COMPLETED: May 2, 1992

BRITO OIL COMPANY, INC.
WALKER #1-26
NW SW NE
Sec. 26, T16S, R20W
Rush County, Ks.

0 - 1260'	Surface Soil, Shale, Shells, Sand
1260 - 1353'	Red Bed
1353 - 1388'	Anhydrite
1388 - 1780'	Shale
1780 - 2120'	Shale w/lime streaks
2120 - 3144'	Shale & Lime
3144 - 3466'	Lime & Shale
3466 - 3731'	Lime
3731 - 3773'	Shale & Lime
3773 - 3866'	Lime, Shale & Chert
3866 - 3880'	Dolomite
3880'	RTD

ELEVATION: 2122' K.B.

Surface Pipe: Set used
8-5/8", 28# pipe @231'
w/135 sacks 60/40 pozmix
2% gel 3% cc.

A F F I D A V I T


STATE OF KANSAS
COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 2nd day of May 1992.

RECEIVED
KANSAS CORPORATION COMMISSION



Paula Ann Laudon
Notary Public

MAY 22 1992

CONSERVATION DIVISION
WICHITA, KS