

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado - Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-165-21,559

LEASE NAME Elmore 0000

WELL NUMBER A-1

3630 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 26 TWP. 16 RGE. 20(X) or (W)

COUNTY Rush

Date Well Completed 5-29-91

Plugging Commenced 1:30 PM

Plugging Completed 3:30 PM

9-28-94 (date)

Wichita State Office Bldg
 130 S. Market Rm 2018
 Wichita 67202-3202
 TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Ummels Tank Service

ADDRESS Box 37

PHONE# (913) 481-2316 OPERATORS LICENSE NO. 4011

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/1/90

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top 3868 Bottom 3878 T.O. 3945

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|------|-------|--------|------------|
| Arbuckle | oil | 0 | 3944 | 5 1/2 | 3944 | 0 |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
5 1/2" casing at 3944' w/ 150 SX Cement, PBTD 3922', Perfs at 3868-78', DU Tool at 1260' w/ 275 SX Cement
1st Plug Pump in 5 1/2" casing with 200# hulls, 50 SX Cement, 20 SX Gel, 100 SX Cement 50" Hulls, 110 SX Cement
Pump Pressure 0-1500 PSI shut in 1000# - 2nd Plug pumped in 8 3/8 X 5 1/2 Annulus with 15 SX Cement
Shut in Pressure 500# Used 65/35 Pozmix 670 Gel
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. _____

Address Ness City, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L. Dean Ummel

STATE OF Kansas COUNTY OF Ness, ss.

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 14 1994

(Employee of Operator or Independent Contractor) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) L. Dean Ummel

(Address) Box 37 Brownell Kansas 67521

SUBSCRIBED AND SWORN TO before me this 16th day of NOV, 19 94

NOTARY PUBLIC - State of Kansas
 M. J. PFANNENSTIEL
 My Appl. Exp. 5-3-98
 My Commission Expires: _____

X M. J. Pfannenstiel
 Notary Public
5-3-98