

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD

RUSH County, Sec. 26 Twp. 16S Rge. 20W (NE) (SW)

Location as "NE/CNW/SE" or footage from lines NE/4  
Lease Owner CHIEF DRILLING CO., INC.

Lease Name WALKER Well No. #1

Office Address 905 CENTURY PLAZA WICHITA, KS. 67202

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed 11-5-81 19

Application for plugging filed 11-5-81 19

Application for plugging approved 11-5-81 19

Plugging commenced 11-5-81 19

Plugging completed 11-5-81 19

Reason for abandonment of well or producing formation DEY

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ?

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3862 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	274'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged w/70 sks @ 720', 40 sks @ 270', 10 sks @ 40',  
5 sks. Rat hole, 5 sks. mouse hole, 130 sks. total, 50-50 pos mix,  
4% gel, 3% c.c., started 8:00 a.m. Completed 10:00 a.m.

STATE OF KANSAS  
11-12-81

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor WARRIOR DRILLING CO.

Address 905 Century Plaza, Wichita, Ks. 67202

STATE OF KANSAS, COUNTY OF SEDGWICK ss.

F.W. Shelton, Jr.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *F.W. Shelton, Jr.*


905 Century Plaza, Wichita, Ks. 67202

(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of November 19 81

*Martha E. Gustin*  
Martha E. Gustin Notary Public.

My commission expires



15.165.20940.0000

WELL LOG

CHIEF DRILLING CO., INC.  
905 Century Plaza  
Wichita, Kansas 67202

CONTRACTOR: WARRIOR DRILLING CO. COMMENCED: 10-26-81  
CASING RECORD: 7 jts. 274', new 20# 8 5/8" set @ 285' COMPLETED: 11-5-81  
cemented w/190 sx. common, 3% c.c., 2% gel.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATIONS</u>
Surface Clay	0	285	2107 GR.
Sand & Clay	285	1390	2111 D.F.
Clay & Sand	1390	2390	2114 K.B.
Sand & Shale	2390	3071	
Shale	3071	3515	
Shale & Lime	3515	3684	
Lime & Shale	3684	3844	
Lime	3844	3862	
RTD	3862		

D & A


STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the NE/4 SEC 26-16S-20W County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

*F. W. Shelton, Jr.*  
F. W. Shelton, Jr., Vice President

Subscribed and sworn to before me this 9th day of November.



Martha E. Gustin Notary Public