


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Rush County. Sec. 20 Twp. 16 Rge. (E) 20 (W)
Location as "NE/CNWKSWK" or footage from lines C NW SW
Lease Owner Pickrell Drilling Company
Lease Name North "A" Well No. 1
Office Address 705 4th National Bank Bldg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 14, 1965
Application for plugging filed January 14, 1965
Application for plugging approved January 14, 1965
Plugging commenced January 14, 1965
Plugging completed January 14, 1965
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4150 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	272'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 240'. Set plug, cemented with

25 sacks cement. Heavy mud to 40'. Set plug,

cemented with 10 sacks cement to bottom of

cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 27 1965

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 4th National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. Sebitts

(owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

C. W. Sebitts
705 4th National Bank Bldg, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of January, 1965

My commission expires June 21, 1966

Maxine Blackman, Notary Public.

15.165-30001-0000
ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY
705 4th National Bank Bldg.
Wichita, Kansas

Rotary Drilling Commenced 1-4-65

Rotary Drilling Completed 1-14-65

LOCATION: North "A" No. 1, C NW SW Section 20-16-20W, Rush County, Kansas.

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (13 jts) 8 5/8" surface casing set at 272' cemented with 165 sacks cement. Circulated. Completed 5:30 P.M. January 4, 1965. No oil string run. D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

20	Top Soil & Clay	C. F. S.
220	Shale & Shells	4000 4050
880	Shale	4010 4060
1100	Sand	4015 4070
1435	Red Beds, Shale & Shells	4037 4092
1470	Anhydrite	4125
2005	Shale & Shells	
2300	Lime & Shale	Slope Test
2690	Lime	2500
2900	Lime & Shale	3000
3050	Shale	3500
3320	Shale & Lime	4000
3422	Shale	
3488	Lime & Shale	
3550	Sandy Lime & Shale	S. L. M.
3735	Shale & Lime	3650
3860	Lime	4005
3941	Lime & Shale	4300
3965	Lime & Chert	
4000	Lime, Chert & Shale	
4048	Shale & Lime	
4150	R.T.D.	

RECEIVED
STATE COMPTROLLER'S OFFICE

JAN 27 1965

CONSERVATION DEPT.
WICHITA, KANSAS

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. SEBITS, Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 18th day of January, 19 65, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

Maxine Blackman
Maxine Blackman, Notary Public