

15-165-00139-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rush County. Sec. 21 Twp. 16S Rge. 20 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SW/4 SW/4 NE/4
Lease Owner Don E. Pratt
Lease Name Campbell Well No. 1
Office Address Box 656, Hays, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-13 19 58
Application for plugging filed 11-13 19 58
Application for plugging approved 11-13 19 58
Plugging commenced 11-13 19 58
Plugging completed 11-13 19 58
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4124 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUG AT 550' AND 20 SACKS CEMENT MIXED AND Poured THROUGH
THE DRILL PIPE.
PLUG AT 180' AND MIX 15 SACKS AND POUR THROUGH THE DRILL PIPE.
PLUG AT 40' - HULLS AND 10 SACKS CEMENT.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor MastDrilling, Inc.
Address P.O. Box 33, Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss. Contractor
James J. Thoman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained, and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James J. Thoman
JAMES J. THOMAN, Secty. Treas.
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of November, 19 58

My commission expires 8-9-62
Betty Jean Galyardt
Notary Public.

PLUGGING
FILE SEC 2116 R 20W
BOOK PAGE 149 LINE 2

DEC 2 1958
CONSERVATION DIVISION

15.165-00139-0000

WELL LOG

OPERATOR: Don E. Pratt
Box 656
Hays, Kansas

CONTRACTOR: Mast Drilling, Inc.
Russell, Kansas

LEASE: Campbell No. 1
SW/4 SW/4 NE/4
Sec. 21-165-20W
Rush County, Kansas

COMMENCED: 11-2-58

COMPLETED: 11-13-58

FORMATION	DEPTH
Clay	20
Shale & Sand	50
Gray Shale	80
Shale & Shells	220
Shale	595
Sand	680
Sand & Shale	1125
Red Bed	1416
Anhydrite	1456
Shale & Shells	1660
Shale-Lime-Shells	1905
Shale & Lime	2130
Lime	2460
Shale & Lime	3417
Lime	3514
Keebner	3519
Lime	3826
Lime & Shale	3863
Lime	3895
Lime & Chert	3930
Lime-Shale-Chert	3960
Lime & Sand	3973
Conglomerate	4013
Mississippi Lime	4051
Lime - Chert	4087
Arbuckle	4124
TOTAL DEPTH	4124

I hereby certify that the above is true and correct to the best of my knowledge.

Mast Drilling, Inc.

James J. Thoman
JAMES J. THOMAN, Secty-Treas.

STATE OF KANSAS)
)ss
COUNTY OF RUSSELL)

Subscribed and sworn to before me this 28th day of November, 1958.

Betty Jean Galbreath
Notary Public

My Commission expires 8-9-62

RECORDED
STATE COMMISSION

DEC 1 1958
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 21 T 16 R 20W
BOOK PAGE 149 LINE 2