


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Rush County. Sec. 16 Twp. 16S Rge. 20 (E) (W)^X
Location as "NE/CNW/SW" or footage from lines SE NE SE
Lease Owner Pickrell Drilling Company
Lease Name Bisagno Well No. 1
Office Address 705 4th National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9/28/68 19__
Application for plugging filed 9/28/68 19__
Application for plugging approved 9/28/68 19__
Plugging commenced 9/28/68 19__
Plugging completed 9/28/68 19__
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3984 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	243'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy Mud to 720'. Set Plug. Cemented with 70

sacks cement. Heavy mud to 240'. Set plug. Cemented

with 20 sacks. Heavy mud to 40'. Set plug. Cemented

with 10 sacks cement to bottom of cellar. Plugged

rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 8 - 1968

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company
Address 705 4th National Bank Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

C. W. Sebitts

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) C. W. Sebitts

705 4th National Bank Building, Wichita, Kansas
(Address)

Subscribed and sworn to before me this 3rd day of October, 19 68

L. M. Whiting
Notary Public.

My commission expires May 20, 1970



15.165-20178-0000
ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY

Rotary Drilling Commenced 9-21-68

705 4th National Bank Building, Wichita, Kansas

Rotary Drilling Completed 9-28-68

LOCATION: Bisagno "A", SE NE SE Sec. 16-16S-20W
Rush County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: Run 6 jts. used 20# 8 5/8" casing 243' set @ 243' K.B.. 155 sacks
cement. 6 hr. Compl. 3:30 P.M. Circ. September 21, 1968 No
oil, string run. D & A

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

70	Clay & Lime, Shells	C. F. S.
243	Shale & Shells, cement	
720	Shale	3950
885	Red Bed	3956
1095	Sand	
1245	Shale & Shells	
1431	Shale	
1468	Anhydrite	
1660	Shale	Slope Tests
2510	Lime & Shale	2000
2605	Lime	2500
3220	Shale & Lime	3000
3380	Sand, Lime & Shale	3500
3543	Shale & Lime	
3975	Lime +-	S. L. M.
3984	TD	3543
		No difference

RECEIVED
STATE CORPORATION COMMISSION
OCT 8 - 1968
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS

COUNTY OF RUSS

ss.:

On this 10 day of October, 19 68, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of said company, for the uses and purposes therein set forth.

Under my hand and seal of office the day and year last above written.

My commission expires: May 10, 1970

L. M. Whiting
L. M. Whiting Notary Public