

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-165-21,609-0000

LEASE NAME Keough

WELL NUMBER 1

585 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 11 TWP. 16 RGE. 20 (E) or (W)

COUNTY Rush

Date Well Completed 04-25-92

Plugging Commenced 04-25-92

Plugging Completed 04-25-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Carmen Schmitt, Inc.

ADDRESS P.O. Box 47 Great Bend, KS 67530

PHONE#(316) 793-5100 OPERATORS LICENSE NO. 6569

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 04-24-92 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filled? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3980

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Bottom Plug: @ 1450' w/50 sacks cement thru drill pipe

Next Plug: @ 700' w/80 " " " " " 15 sacks in Rat Hole

Next Plug: @ 220' w/40 " " " " "

Top Plug: @ 40' w/10 " " " " "

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Carmen Schmitt

STATE OF Kansas COUNTY OF Barton, ss.

Carmen Schmitt (Employee of Operator) or (Conservation Division) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed with the State Corporation Commission, and that the same are true and correct, so help me God.

(Signature) Carmen Schmitt

(Address) P.O. Box 47, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 20 day of May, 19 92

Kathleen Hirschmann
Notary Public

My Commission Expires: _____



RECEIVED
STATE CORPORATION COMMISSION
JUN 3 1992
CONSERVATION DIVISION
Wichita, Kansas 67202

DRILLER'S WELL LOG

DATE COMMENCED: April 20, 1992
DATE COMPLETED: April 25, 1992

Carmen Schmitt, Inc.
KEOUGH NE #1
75'W of C-W/2-SW-SE
Sec. 11, T16S, R20W
Rush County, Ks.

0 - 1280' Surface Soil, Sable, Shells, Sand
1280 - 1410' Red Bed
1410 - 1449' Anhydrite
1449 - 1870' Shale
1870 - 2210' Shale w/lime streaks
2210 - 3215' Shale & Lime
3215 - 3512' Lime
3512 - 3556' Shale & Lime
3556 - 3811' Lime
3811 - 3960' Shale, Lime, Chert, Sand
3960 - 3980' Dolomite
3980' RTD

ELEVATION: 2164 K.B.

Surface Pipe: Set new
8-5/8", 20# pipe @217'
w/135 sacks 60/40 pozmix
2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Subscribed and sworn to before me this 27th day of April, 1992.

