

15-165-20053-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Rush County, Sec. 10 Twp. 16S Rge. (E) 20W (W)

Location as "NE/CNW%SW%" or footage from lines SW SE SW

Lease Owner Pickrell Drilling Company

Lease Name Moran "A" Well No. 1

Office Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 31, 19 67

Application for plugging filed August 31, 19 67

Application for plugging approved August 31, 19 67

Plugging commenced August 31, 19 67

Plugging completed August 31, 19 67

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey

Producing formation Depth to top Bottom Total Depth of Well 3992 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	236'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

SEP 18 1967

Heavy mud to 800'. Set plug. Cemented with 100 sacks. cement. Heavy mud to 240'. Set plug. Cemented with 25 sacks cement. Heavy mud to 40'. Set plug. Cemented with 10 sacks to bottom of cellar. Plugged rat hole with 2 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
C. W. Sebitts

(owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 Fourth National Bank Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of September, 19 67

L. M. Whiting
Notary Public.

My commission expires May 10, 1970

15-165-20053-0000
ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Bldg.
Wichita, Kansas 67202
Rotary Drilling Commenced 8/23/67

LOCATION: Moran "A" No. 1
SW SE SW Section 10-16S-20W
Rush County, Kansas
Rotary Drilling Completed 8/31/67

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (11 jts.) 8 5/8" casing set at 236' and cemented with 140 sacks cement.
Circulated. Completed 5:00 PM, 8/23/67. No oil string was run. D. & A.,
plugged 8/31/67.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

860	Shale & Shells		
1150	Sand	<u>C. F. S.</u>	
1415	Shale & Shells	3600'	
1457	Anhydrite	3765'	
2080	Shale & Shells	3940'	
2185	Lime & Shale	3950'	
2358	Lime w/Shale Streaks	3960'	
2525	Lime	3992'	
2670	Lime & Shale		
2840	Lime w/Shale Streaks		
3547	Lime & Shale	<u>Slope Tests</u>	
3901	Lime	2500'	
3922	Chert	3000'	
3942	Lime & Chert	3500'	
3992	Sand & Chert, RTD		
		<u>S. L. M.</u>	
	Board	3431.52	
	Strap	3429.69	
	Diff.	1.83	(No Corr.)

SEP 18 1967
CONSERVATION DIVISION
WICHITA, KANSAS

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By C. W. Sebitts, Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 12th day of September, 19 67, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: May 10, 1970

L. M. Whiting
Notary Public