

15.165-00013-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Rush County. Sec. 21 Twp. 16 Rge. 20 (E) (W) W

Location as "NE/CNWxSWx" or footage from lines NE-NE-NE

Lease Owner Heathman & Company

Lease Name Campbell Well No. 1

Office Address 254 N. Washington, Wichita 7, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 7-27 19 52

Application for plugging filed 7-27 19 52

Application for plugging approved 7-27 19 52

Plugging commenced 7-27 8:00 A. M. 19 52

Plugging completed 7-27 4:00 P. M. 19 52

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes Verbal

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4028 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Blue Shale & Shells		0	167'	8 5/8	167'	None
Anhydrite	•	1425	3218			
Lansing		3520	3820			
Base K. C.		3820	3978			
Arbuckle		3978	4028			
Total Depth		4028				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Stirred pits well, filled hole with heavy muc to 165'. Set Bottom wood plug. Ran 1/2 sack hulls and 15 sacks of cement on same. Filled hole with Heavy mud to 35' set top wood plug. Ran 1/2 sack hulls and 10 sacks of cement, filling to the bottom of the cellar.

RECEIVED
STATE CORPORATION COMMISSION

Name of Plugging Contractor Strain Drilling Co. (If additional description is necessary, use BACK of this sheet)
Address Box 188 Hays, Kansas JUL 30 1952 7-30-52
CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas, COUNTY OF Ellis, ss.

_____(employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. P. Strain
Box 188 Hays, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of July, 19 92
Mildred Schneider
Notary Public.

My commission expires March 26, 1956

24-2675-8 2-52-20M

PLUGGING
FILE SEC 21 T 16 R 20
BOOK PAGE 33 LINE 21

15-1165-00013-0000

WELL LOG

COMPANY: Heathman & Company

NE-NE-NE Sec. 21
Twp 16, Rge. 20W
Rush County, Kansas

LEASE: Campbell # 1

ELEVATION: 2173 R. B.

NOTE: All meas. Rotary Bushing.

0	120 Post Rock & Shale
120	167 Blue Shale & Shells
167	400 Shale
400	650 Shale
650	860 Sand & Shale
860	1090 Sand
1090	1285 Shale & Shells & Redbed
1285	1425 Shale & Redbed
1425	1464 Anhydrite
1464	1690 Shale & Shells
1600	1980 Shale & Shells
1980	2160 Shale & Lime
2160	2245 Shale & Lime
2245	2380 Shale & Lime
2380	2440 Lime & Shale
2440	2515 Lime & Shale
2515	2580 Lime & Shale
2580	2630 Lime & Shale
2630	2750 Shale & Lime
2750	2860 Lime & Shale
2860	2950 Lime & Shale
2950	3115 Shale & Shells
3115	3225 Shale & Lime
3225	3305 Lime & Shale
3305	3363 Lime & Shale
3363	3400 Lime
3400	3425 Lime
3425	3515 Lime
3515	3555 Lime
3555	3591 Lime
3591	3595 Lime
3595	3650 Lime
3650	3700 Lime
3700	3745 Lime
3745	3782 Lime
3782	3825 Lime
3825	3875 Cherty Lime
3875	3905 Chert & Lime
3905	3927 Lime

3927	3945 Lime
3945	3973 Lime & Shale
3973	3978 Lime & Shale
3978	4020 Arbuckle
4020	4028 Arbuckle
4028	(Total Depth)

COMMENCED: 7-14-52
COMPLETED: 7-27-52

Casing Record:

8 5/8 Surface Casing set at 167' W/115 Sacks of Cement by Sun Cementing Co.

D. S. T. by Johnston Testers

3573-3591 Tool open 45 Min. weak blow Recovered 6' of Drilling Mud oil spotted on top B.H.P. 15 Min. 0

3917-3927 Tool open 1hour & 15 min. Recovered 120' of Muddy salt water with a slight show of oil B.H.P. 1150#

Schlumberger Log Run

Geologist

Bob Armstrong
Warren Spaulding

TOPS:

Anhydrite	1425
Topeka	3218
Heebner	3504
Toronto	3627
Lansing	3546

RECEIVED
STATE CORPORATION COMMISSION
JUL 27 1952
CONSERVATION DEPARTMENT
WICHITA, KANSAS

Base K.C.	3820
Marmaton Chert	3848
Conglomerate	3923
Arbuckle	3978
Total Depth	4028

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Campbell # 1, located NE-NE-NE, Sec. 21, Twp 16, Range 20W, Rush County, Kansas

CONTRACTOR Strain Drilling Co.

By. *T. C. Strain*
T. C. Strain

PLUGGING
FILE SEC 21 T 16 R 20W
BOOK PAGE 33 LINE 21

Subscribed and sworn to before me this 28th day of July 1952

My Commission expires March 26, 1952

Notary Public

Mildred Schneider