

K-1165-20232-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Rush County, Sec. 4 Twp. 16S Rge. (X) 20W  
Location as "NE/CNW/SW" or footage from lines NW NW NE  
Lease Owner E. K. Edmiston  
Lease Name Bullock Well No. 1  
Office Address 801 First Natl Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil well  
Date well completed April 26, 19 69  
Application for plugging filed February 3, 19 71  
Application for plugging approved February 4, 19 71  
Plugging commenced February 11, 19 71  
Plugging completed February 17, 19 71  
Reason for abandonment of well or producing formation  
Production below economic level.  
If a producing well is abandoned, date of last production January 27, 19 71  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Kansas City Depth to top 3788 Bottom Total Depth of Well 4000 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	200'	None
				5-1/2"	3698'	3153'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom. Ran plug to 3500'. Ran 5 sacks of cement from 3500' to 3470'.

Plugged off top. Sun Cementing pumped 20 sacks gel, 3 sacks of hulls & 140 sacks of cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn & Smith Pipe Pulling Co.  
Address P. O. Box 156, Ellinwood, Kansas 67526

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Robt. K. Edmiston (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
801 First Natl Bank Bldg., Wichita, Ks.  
(Address)

AND SWORN TO before me this 26th day of March, 19 71

[Signature]  
Marilyn E. Fox  
Notary Public.

My commission expires November 9, 1973



K-165-20232-0000

GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

BULLOCK #1  
NW NW NE Section 4-16S-20W  
Rush County, Kansas

Commenced: April 13, 1969  
Completed: April 26, 1969

OPERATOR - E. K. Edmiston Drilling Co., Inc.

DEPTH		FORMATION	REMARKS
From	To		
0	200	Surface clay and shale	Ran 5 joints of 8-5/8" casing, set @ 200' w/150 sacks cement.
200	700	Shale and shells	
700	920	Shale, shells and sand	
920	1050	Sand	
1050	1258	Shale	
1258	1445	Shale and red bed	
1445	1452	Shale	
1452	1492	Anhydrite	
1492	1930	Shale	
1930	2080	Shale and shells	
2080	3560	Lime and shale	
3560	3797	Lime	
3797	3876	Lime and chert	
3876	3950	Lime	
3950	4000	Conglomerate	
4000	TD		Ran 117 joints of 5-1/2" casing, set @ 3698' w/90 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 4 1971  
CONSERVATION DIVISION  
Wichita, Kansas

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the NW NW NE Section 4-16S-20W, Rush County, Kansas to the best of my knowledge and belief.

E. E. Hall  
E. E. HALL

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

Before me, the undersigned, a Notary Public within and for said County and State, on this 29 day of April, 1969, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972.

Barbara J. Layton  
Barbara J. Layton, Notary Public

