

15.665-20166-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Rush County, Sec. 5 Twp. 16S Rge. 20 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines SW SW

Lease Owner Barnett Oil Company  
Lease Name Royce Well No. 1  
Office Address 411 First National Bank Bldg. - Wichita, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed July 5 1968  
Application for plugging filed July 5 1968  
Application for plugging approved July 5 1968  
Plugging commenced July 5 1968  
Plugging completed July 5 1968  
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4110 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	250'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Lay down drill pipe  
& plug hole 1st plug  
@ 1190' w/90 sx, 2nd  
plug @ 240 w/25 sx, 3rd  
plug @ 40 w/10 sx

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 10 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Red Tiger Drilling Company  
Address 1720 Wichita Plaza - Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Harold R. Martin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold R. Martin  
1720 Wichita Plaza - Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of July, 19 68

My commission expires 3-22-71

Betty M. Massey Notary Public.

DRILLERS LOG

No. 1 Royce

CASING RECORD:	COMPANY:	Barnett Oil Company	DESCRIPTION:
8 5/8" @ 250'	CONTRACTOR:	Red Tiger Drilling Company	SW SW of
w/185 sx cement	COMMENCED:	June 24, 1968	5-16S-20W
TOTAL DEPTH: 4110'	COMPLETED:	July 5, 1968	Rush County,
			Kansas
			ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay and sand	0	70	
Shale	70	780	
Shale and Red Bed & sand	780	915	
Sand	915	1188	
Red Bed and Shale	1188	1445	
Shale	1445	1515	
Anhydrite	1515	1555	
Shale	1555	1725	
Shale and Shells	1725	2260	
Shale and Shells	1725	2260	
Lime and Shale	2260	2420	
Lime	2420	2800	
Lime and Shale	2800	3435	
Lime	3435	3960	
Lime and Chert	3960	4000	
Chert	4000	4020	
Cherty Lime	4020	4035	
Lime, chert & sand	4035	4080	
Chert and Dolomite	4080	4110	

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 10 1968  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

*Harold R. Martin*  
Harold R. Martin

Subscribed and sworn to before me this 8th day of July, 1968.

*Betty M. Maloney*  
Notary Public

My Commission Expires:

3-22-71