


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ness County, Sec. 6 Twp. 20S Rge. 23W (E) (W)

Location as "NE/CNW/SE/SW" or footage from lines. N/2 SW NW

Lease Owner Twin Western Resources, Inc.

Lease Name Miner Well No. 1

Office Address 920 Union Center Bldg.- Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9/9/77 19

Application for plugging filed 9/9/77 19

Application for plugging approved 9/9/77 19

Plugging commenced 9/9/77 19

Plugging completed 9/9/77 19

Reason for abandonment of well or producing formation

Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Depth to top Bottom Total Depth of Well 4460 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	368'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st Plug @ 600' w/70 sx

2nd Plug @ 240' w/20 sx

3rd Plug @ 40' w/10 sx

9-19-77

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Thunderbird Drilling, Inc.

Address P. O. Box 18407- Wichita, Kansas 67218

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Burke Krueger

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

P. O. Box 18407- Wichita, Kansas 67218

SUBSCRIBED AND SWORN TO before me this 16th day of September, 1977

My commission expires 3-25-80

Gloria DeJesus
Gloria DeJesus

Notary Public.



DRILLERS LOGCompany Twin Western Resources, Inc. Contractor Thunderbird Drilling, Inc.Elevation 2316' K.B.
2311 Gr.Farm MinerWell No. 1Casing 8 5/8" @ 368' w/250 sxLocation N/2 SW NW
Sec. 6-20S-23WCounty Ness County, KansasProduction

<u>From</u>	<u>To</u>	<u>Description</u>
0	295	Surface Hole
295	960	Shale
960	1035	Shale & Sand
1035	1255	Sand
1255	1603	Shale & Shells
1603	1639	Anhydrite
1639	2760	Shale & Shells
2760	2775	Shale & Lime
2775	3205	Shale & Shells
3205	3395	Shale
3395	4070	Shale & Lime
4070	4150	Lime & Shale
4150	4240	Shale & Lime
4240	4350	Lime & Shale
4350	4460	Lime
4460		R.T.D.

STATE OF KANSAS)
) ss.
COUNTY OF SEDGWICK)

I, Burke Krueger, of Thunderbird Drilling, Inc. upon oath states
that the above and foregoing is a true and correct copy from the Daily Drilling
Report from your #1 Miner _____.

Burke Krueger

Subscribed and sworn to before me this 16th day of September, 1977.

Gloria DeJesus
Gloria DeJesus Notary Public

My commission expires: 3-25-80

