


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Ness County. Sec. 6 Twp. 20S Rge. 23W E/W  
Location as "NE/CNW/SW" or footage from lines \_\_\_\_\_

C-SE NE  
Lease Owner Associated Petroleum Consultants, Inc.  
Lease Name Zimmerman Well No. 1  
Office Address 645 R. H. Garvey Bldg., Wichita, Kansas  
Character of Well (Completed as Oil, Gas or Dry Hole) 67202



Locate well correctly on above  
Section Plat

Dry Hole  
Date Well completed June 2, 19 79  
Application for plugging filed Verbal Application 19\_\_  
Application for plugging approved Verbal Approval 19\_\_  
Plugging commenced June 2, 19 79  
Plugging completed June 2, 19 79  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marvin Schmidt  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4,460'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	623'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy rotary mud from 4,460 ft. (rotary total depth) to 620 ft. Set plug at 620 ft. and cemented with 50 sacks cement. Filled hole with heavy rotary mud from 620 ft. to 300 ft. Set plug at 300 ft. and cemented with 35 sacks cement. Filled hole with heavy rotary mud from 300 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Sun Oilwell cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oilwell Cementing, Inc.  
Box 169, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Dean Britting, Agent ~~XXXXXX~~ of owner ~~XXXXXXXXXXXXXXXXXXXX~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting  
200 N. Main, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of June, 19 79

Elsie Willison  
Elsie Willison - Notary Public.

My commission expires July 25, 1982

KANSAS DRILLERS LOG

COMPANY Associated Petroleum Consultants, Inc. SEC. 6 T. 20S R. 23W  
FARM Zimmerman NO. 1 LOC. C-SE NE

COUNTY Ness

ROTARY TOTAL DEPTH 4,460'  
COMM. May 24, 1979 COMP. June 2, 1979  
CONTRACTOR H-30, Inc. (Rig #3)  
ISSUED June 3, 1979

CASING

10 3/4"  
8 5/8" Set at 623' cemented w/325 sxs cement  
5 1/2"  
4 1/2"

ELEVATION 2,303' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale	1,510'
Red Bed and Anhydrite	2,020'
Shale and Lime	4,045'
Lime and Shale	4,460'
Rotary Total Depth	4,460'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting  
Dean Britting

State of Kansas )  
County of Sedgwick ) SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 8th day of June, 1979.

RECEIVED  
STATE OF KANSAS  
JUN 11 1979  
NOTARY PUBLIC  
STATE OF KANSAS

Elsie Willison  
Elsie Willison - Notary Public

My Commission Expires:  
July 25, 1982