

15.135-2A29-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

Ness County, Sec 4 Twp 20 Rge (E) 23W (W)  
Location as "NE/CNW/SE" or footage from lines SW NE SE

Lease Owner DONALD C. SLAWSON  
Lease Name McCune 'A' Well No. 1  
Office Address 200 Douglas Building Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed January 10, 19 81  
Application for plugging filed January 10, 19 81  
Application for plugging approved January 10, 19 81  
Plugging commenced January 9, 19 81  
Plugging completed January 10, 19 81  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plot

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4480 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	531.08'	surface	538'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

1st plug @ 800' w/70 sx  
2nd plug @ 480' w/25 sx  
Bridge plug @ 40' w/10 sx  
5 sx in Rat Hole

Name of Plugging Contractor ALLIED CEMENTING CO., INC.  
Address Box 31 Russell, Kansas 67665  
(If additional description is necessary, use BACK of this sheet)

STATE OF KANSAS, COUNTY OF SEDGWICK ss.  
James C. Remsberg

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *James C. Remsberg*  
JAMES C. REMSBERG, Oper. Mgr.  
200 Douglas Bldg. Wichita, KS 67202  
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of February, 19 81

My commission expires 6/12/82



*Sherry L. Kendall*  
SHERRY L. KENDALL  
Notary Public.

02-23-81

WELL LOG

OPERATOR: DONALD C. SLAWSON  
 200 DOUGLAS BUILDING  
 WICHITA, KANSAS 67202

LEASE: #1 McCune 'A'  
 SW NE SE Sec. 4-20-23W  
 Ness County, Kansas

CONTRACTOR: SLAWSON DRILLING COMPANY, INC.  
 200 DOUGLAS BUILDING  
 WICHITA, KANSAS 67202

COMMENCED: December 31, 1980

COMPLETED: January 10, 1981

CASING: Surface - 8 5/8" @ 538" w/350 sx 60/40 poz

0 - 540 Surface  
 540 - 1504 Shale  
 1504 - 1556 Anhydrite  
 1556 - 2995 Shale  
 2995 - 3731 Lime and shale  
 3731 - 3930 Lime  
 3930 - 4060 Lime and shale  
 4060 - 4255 Lime  
 4255 - 4310 Lime and shale  
 4310 - 4450 Lime  
 4450 - 4480 Mississippi  
 4480 RTD

STATE OF KANSAS )  
 COUNTY OF SEDGWICK )


SS.

REVISION  
 FEB 9 1981

I, James C. Remsberg, OF THE SLAWSON DRILLING COMPANY, INC.  
 UPON OATH STATE THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE  
 LOG OF THE #1 McCune 'A' TEST.

*James C. Remsberg*  
 JAMES C. REMSBERG, President

SUBSCRIBED AND SWORN TO BEFORE ME THIS 19th DAY OF February, 1981



*Sherry L. Kendall*  
 SHERRY L. KENDALL, Notary Public

MY COMMISSION EXPIRES : 6/12/82