

15-135-20983-0000

STATE OF KANSAS  
CORPORATION COMMISSION


Form CP-4

Give Address of Completely  
Make Requirements  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Ness County, Sec 4 Twp. 20S Rge. (E) 23 (W)

Location as "NE/CNW/SE/SW" or footag. from lines C NE SW  
Lease Owner O. A. Sutton  
Lease Name Mauler Well No. 1  
Office Address 800 Sutton Place, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 22 1975  
Application for plugging filed July 22 1975  
Application for plugging approved July 22 1975  
Plugging commenced July 22 1975  
Plugging completed July 22 1975  
Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Depth to top Bottom Total Depth of Well 4445 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	366'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug at 600' with 70 sacks 50-50 Pozmix; plug at 240' with 20 sacks; plug at 40' with 10 sacks. Job by Halliburton. Complete at 10:55 p.m. 7-22-75.

STATE OF KANSAS  
CORPORATION COMMISSION

AUG 14 1975

CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.  
Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Jack G. Paulsen (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack G. Paulsen  
800 Sutton Place, Wichita, Kansas 67202 (Address)

SUBSCRIBED AND SWORN TO before me this 13th day of August, 1975.

My commission expires June 28, 1978. Jean S. Taylor Notary Public.

15-135-20983-0000

GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

Mauler #1  
C-NE-SW Sec 4-20S-23W  
Ness County Kansas

Commenced: 7-9-75

Completed: 7-22-75

OPERATOR: O. A. SUTTON

Depth,		Formation	Remarks
From	to		
0	370	Surface Clay-Sand-Blue Shale	
370	881	Shale	Ran 9 jts of used 28# 8 5/8"
881	889	Blaine Anhy	csg set @ 366' Cemented w/
889	950	Shale	225 sks Common 2% Gel
950	1180	Sand	3% CC PD @ 9:30 p.m. 7-9-75
1180	1511	Shale	
1511	1554	Anhy	
1554	1834	Shale-Redbed	
1834	2070	Shale	
2070	3917	Lime-Shale	
3917	4414	Lime	
4414	4445	Lime-Chert	
	4445 - TD		DRY & ABANDONED

I, James S. Sutton II, certify this is a correct copy of the Drillers' Well Log for the well drilled C-NE-SW Sec 4-20S-23W, Ness County, Kansas, to the best of my knowledge and belief.

*James S. Sutton II*  
JAMES S. SUTTON II


STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State on this 5th day of August, 1975, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

*Elizabeth J. Edwards*  
ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission Expires: February 6, 1979.



RECEIVED  
STATE OF KANSAS  
AUG 14 1975  
CONSERVATION DIVISION  
Wichita, Kansas