


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Ness County, Sec. 9 Twp. 20S Rge. 23W (E) (W) X
Location as "NE/CNW/SW" or footage from lines C SW NE
Lease Owner Cities Service Oil Company
Lease Name Kanaga "A" Well No. 1
Office Address 710 Sutton Place Building, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed May 1 19 73
Application for plugging filed May 1 19 73
Application for plugging approved May 1 19 73
Plugging commenced May 1 19 73
Plugging completed May 1 19 73
Reason for abandonment of well or producing formation D & A



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4470 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	523'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole to 535' w/heavy mud
Put 50 sx cement, Filled hole
w/heavy mud to 240' Put 25 sx
cement, Filled hole to 40' w/heavy
mud and Put 10 sx cement to bottom
of cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAY 8 1973
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company
Address 1720 Wichita Plaza, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Gloria Fawcett (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gloria Fawcett
1720 Wichita Plaza, Wichita, Kansas 67202
(Address)

Subscribed and sworn to before me this 4th day of May, 19 73
Linda H. Dickens
Notary Public.
March 8, 1977



DRILLERS LOG

No. 1 Kanaga "A"

CASING RECORD:	COMPANY: Cities Service Oil Co.	DESCRIPTION:
8 5/8" @ 523'	CONTRACTOR: Red Tiger Drilling Co.	C SW NE
M/275 sx cement	COMMENCED: April 18, 1973	9-205-23N
	COMPLETED: May 1, 1973	Mass County,
		Kansas
TOTAL DEPTH: 4470'		ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Clay & Rock	0	95	
Sand & Shale	95	340	
Shale	340	525	
Shale & Sand Streaks	525	899	
Blaine Anhydrite	899	912	
Shale & Redbed	912	990	
Sand	990	1200	
Shale	1200	1290	
Shale & Redbed	1290	1548	
Anhydrite	1548	1548	
Shale & Shells	1548	2220	
Shale & Lime	2220	3760	
Lime	3760	4438	
Chert & Lime	4438	4442	
Lime	4442	4470	
Lime & Chert	4470	4470	

RECEIVED
STATE CORPORATION COMMISSION
JUN 27 1973
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
Gloria Fawcett

Subscribed and sworn to before me this 4th day of May, 1973.

Linda H. Dickens
Notary Public

My Commission Expires:

March 8, 1977

