

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-23,532

LEASE NAME Morrison

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

4620' Ft. from S Section Line

1320' Ft. from E Section Line

SEC. 4 TWP. 20 RGE. 23 (E) or (W)

COUNTY Ness

LEASE OPERATOR DaMar Resources, Inc.

ADDRESS Box 70 Hays, Kansas 67601

PHONE#(913) 625-0020 OPERATORS LICENSE NO. 9067

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 12-17-90

Plugging Commenced 12-17-90

Plugging Completed 12-17-90

The plugging proposal was approved on December 13, 1990 (date)

by District #1 (KCC District Agent's Name).

Is ACO-1 filed? no If not, Is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface Pipe	0	510'	8 5/8	11 its.	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Plugs: 1544' 50sks, 800' 80sks, 510' 50sks, 40' 10sks, rat hole 15sks, Total 205sks, 60/40 poz., 6% gel, plug down @ 8:30 P.M. 12-17-90.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Western Kansas Drilling, Inc. License No. 4083

Address P.O. Box 126, Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: DaMar Resources, Inc.

12-21-90

STATE OF Kansas COUNTY OF Ellis

CONSERVATION DIVISION
Wichita, Kansas

DaMar Resources, Inc.

(Employer of Operator) or (Operator) of


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) [Signature]

P.O. Box 70

(Address) 234 W. 11th Hays, KS

SUBSCRIBED AND SWORN TO before me this 19 day of December, 1990



Commission Expires: July 10, 1992

Notary Public

DRILLER'S LOG

Operator: DaMar Resources, Inc.

Contractor: Western Kansas Drilling, Inc.

Well & Well Description: Morrison #1
C-N/2-NE 4-20-23 Ness County, Kansas

Commenced: 12-9-90

Completed: 12-17-90

Character of Well: D & A

Elevation: 2260' G.L., 2265 K.B.

Casing: Ran 11 jts. of 8 5/8's set @ 510'


Figures Indicate Bottom of Formations

0' - 1501'	Sand & Shale
1501' - 1544'	Anhy.
1544' - 2590'	Sand & Shale
2590' - 3220'	Lime & Shale
3220' - 3740'	Lime & Shale
3740' - 4210'	Lime & Shale
4210' - 4390'	Lime & Shale
4390' - 4438'	Miss.

State of Kansas)
County of Ellis) ss:

NOV 21 1990
CORRECTION
Western Kansas

I Stanley Younger, President of Western Kansas Drilling, Inc.
upon oath state that the above and foregoing is a true and correct copy of
the log of the Morrison #1


Stanley Younger, President