


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plot

Ness

County. Sec. 12 Twp. 20 Rge. 23W (E) (W)

Location as "NE/CNWxSWx" or footage from lines C SE SW

Lease Owner Hellar Drilling Company

Lease Name Ripple A#1

Well No.

Office Address Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 2/5/70 19

Plugging completed 2/16/70 19

Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey

Producing formation Depth to top Bottom Total Depth of Well 4375 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	249	none
				4 1/2"	4370	2325'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it to the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked bottom, ran sand to 4350', dumped 4 sacks of cement.

Loaded hole, shot pipe at 3991', 3894', Allied pumped 80 barrels oil

and chased plug to 3800', shot pipe at 3702', 3517', 3419', 3318',

3219', 3118', 3016', let pipe set on tension. Shot pipe at 2917',

2821', 2735', 2634', 2537', 2441', 2343', worked pipe loose and pulled

72 joints. Pumped 15 sacks of gel and 120 sacks of cement to plug well.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

APR 1 - 1970

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.

Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE ss.

NOEL J. KNIGHT

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

CHASE, KANSAS

(Address)

Subscribed and sworn to before me this 17th day of February, 1970

NOTARY PUBLIC
SUSSEX COUNTY, KANSAS
2/15/71

My commission expires

Notary Public.

15-135-20240-0001
ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Bldg.
Wichita, Kansas 67202

Rotary Drilling Commenced 4/2/69
Rotary Drilling Completed 4/14/69

LOCATION: Ripple "A" No. 1
C SE SW Section 12-20S-23W
Ness County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (13 jts.) Used 28# 8 5/8" surface casing set at 249' KB and cemented
with 160 sacks cement. Complete 3:15 PM, 4/2/69. Circulated.

No oil string was run. D. & A., plugged 4/14/69.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

135	Clay & Post Rock	C. F. S.
249	Blue Shale & Cement	4257'
645	Shale & Shells & Clay	4268'
890	Red Bed & Shale	4290'
1100	Shale & Sand, Shells	4335'
1431	Shale & Sand Stringers	4342'
1468	Anhydrite	4350'
1650	Shale	4355'
2115	Shale & Lime	4360'
2533	Lime & Shale	4365'
2540	Shale & Lime	4370'
2675	Lime & Shale	4375'
2955	Shale & Lime	
3125	Shale	
3410	Shale & Sandy Lime	Slope Tests
3551	Shale & Lime	2500'
3575	Shale	3000'
3760	Sandy Lime & Shale	3500'
3920	Lime	4000'
4257	Lime & Shale	
4290	Sand, Shale & Lime	
4320	Lime	S. L. M.
4350	Lime & Shale	
4360	Lime, Shale & Chert	Board 4305.09'
4375	Mississippi, RTD	Strap 4304.42'
		Diff. .67'

*Hole washed down to 4370 & 4 1/2" set @ 4375
on 6/24/69 w/ 75 sac*

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts, Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 22nd day of April, 1969, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact, and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

At my hand and seal of office the day and year last above written.
My commission expires: May 10, 1970

L. M. Whiting
Notary Public

L. M. WHITING