


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Ness County, Sec. 19 Twp. 20S Rge. 23 (E) (W) X

Location as "NE/CNW/SW" or footage from lines C SW NW
Lease Owner R. V. Lehner
Lease Name Strobel Well No. 1
Office Address P. O. Box 398 Ness City, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed 3-19-68 19____
Application for plugging approved 3-20-68 19____
Plugging commenced 4-13-68 19____
Plugging completed 5-8-68 19____

Reason for abandonment of well or producing formation _____
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4391 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	289	None
				4 1/2	None	3601

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved in. Cleaned out cellar. Sanded to 4300'. Dumped 4 sacks of cement. Rigged up unit. Working pipe.

Working pipe. Shot pipe at 3700' and 3620'. Circulating. Spotted 80 bbl. of oil.

Working pipe.

Working pipe. Pulling pipe.

Squeezed well with 30 sacks of mud - 5 sacks of hull and 150 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 15 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14 day of May, 1968.

My commission expires May 27, 1969

[Signature]
Notary Public.

DRILLERS LOG

#1 Strobel

CAESING RECORD: Ran 288.98' of new 8-5/8" surface casing.	COMPANY: R. V. Lehner	DESCRIPTION: C/SW NW Section 19-20S-23W Wess County, Kansas
TOTAL DEPTH: 4438'	CONTRACTOR: Strata Drilling, Inc.	ELEVATION: 2289' KB
	COMMENCED: February 13, 1968	
	COMPLETED: February 26, 1968	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale & Sand	0	500	Ran 288.98' of new surface casing; set and cemented at 288.98' with 170 sacks of common cement and 2% gel. Plug down at 12:20 P. M. February 15, 1968.
Shale	500	892	
Shale, Shells & Sand	892	1300	
Shale	1300	1513	
Anhydrite	1513	1524	
Yellow Chalk	1524	1534	
Shale & Shells w/Lime	1534	1973	
Shale & Lime	1973	3504	
Chalky Lime	3504	3690	
Lime & Shale	3690	3755	
Lime	3755	4367	
Cherty Lime	4367	4410	
Lime	4410	4438	

Total Depth 4438'

RECEIVED
STATE CORPORATION COMMISSION
MAR 20 1968
CONSERVATION DIVISION
Wichita, Kansas

Ran 4437' of new 4 1/2"; set and cemented at 4437' with 125 sacks of common cement, salt saturated. Plug down at 3:30 A. M. February 26, 1968.

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
Charles W. Steincamp, President

Subscribed and sworn to before me this 26th day of February, 1968.

Elaine H. Taylor
Elaine H. Taylor, Notary Public

