

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Ness County, Sec. 19 Twp. 20S Rge. 23W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
150' N, 50' W of C SW NW


Lease Owner Kinderhook Oil & Gas, Inc.  
Lease Name Strobel "A" Well No. #1  
Office Address 4608 Boulevard Place, Des Moines, Iowa 50311  
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole

Date Well completed January 14, 1978 19  
Application for plugging filed January 14, 1978 19  
Application for plugging approved January 14, 1978 19  
Plugging commenced January 14, 1978 19  
Plugging completed January 14, 1978 19  
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set. Hole plugged with 50-50 pozmix, 6% gel as follows:  
70 sacks @ 550', 20 sacks @ 240', 10 sacks @ 40'. Plug down 4:45 a.m.,  
January 14, 1978.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 09 1978

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling Company


STATE OF Kansas COUNTY OF Barton, ss.  
Kenneth J. Link (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Kenneth J. Link President  
P. O. Box 358, Great Bend, Kansas 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of January, 19 78.

Loneita Barry  
Loneita Barry Notary Public.

My commission expires 3-28-80.



K-135-21401-0000  
DRILLERS LOG

#1 Strobel "A"

CASING RECORD: 297' new 8-5/8" surface casing	COMPANY: Kinderhook Oil & Gas, Inc.	DESCRIPTION: 150' N, 50'W of C SW NW Section 19-20S-23W Ness County, Kansas
TOTAL ROTARY DEPTH: 4381'	CONTRACTOR: Strata Drilling Company	
	COMMENCED: January 7, 1978	
	COMPLETED: January 14, 1978	

D & A

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Post rock	0	80	Ran 7 jts. new 8-5/8" surface casing, set and cemented @ 294' with 185 sacks commoncement, 2% gel, 3% C.C.; cement circulated. Plug down 11:40 p.m., January 7, 1978.
Shale	80	306	
Shale, lime	306	1513	
Anhydrite	1513	1558	
Shale and lime	1558	1710	
Shale	1710	2208	
Shale and lime	2208	4375	
Lime	4375	4381	Ran one drill stem test.
			Hole plugged with 50-50 pozmix, 6% gel as follows: 70 sacks @ 550', 20 sacks @ 240', 10 sacks @ 40'. Plug down 4:45 a.m., January 14, 1978.

RECEIVED  
 STATE CLERK  
 MAR 09 1978  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 )ss  
 COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

*Kenneth J. Link*  
 Kenneth J. Link, President

Subscribed and sworn to before me this 20th day of January, 1978.

My commission expires 3-28-80.

*Lawrence B. ...*