

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Ness County. Sec. 26 Twp. 20S Rge. (E)23 (W)

Location as "NE/CNW&SW" or footage from lines C SW SW

Lease Owner Pickrell Drilling Company

Lease Name Harkness "C" Well No. 1

Office Address 705 4th Nat'l Bank Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 4 19 68

Application for plugging filed March 4 19 68

Application for plugging approved March 4 19 68


Plugging commenced March 4 19 68

Plugging completed March 4 19 68

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Depth to top Bottom Total Depth of Well 4370 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Row 1: SIZE 8 5/8", PUT IN 270, PULLED OUT None.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 600'. Set plug. Cemented with 70 sacks cement. Heavy mud to 240'. Set plug Cemented with 20 sacks cement. Heavy mud to 40'. Set plug. Cemented with 10 sacks cement to bottom of cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAR 18 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company

Address 705 4th National Bank Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. W.H.C. W. SEBITS (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well is filed and that the same are true and correct. So help me God.


(Signature) C. W. Sebitts

705 4th Nat'l Bank Building, Wichita 2, Kans. (Address)

SUBSCRIBED AND SWORN to before me this 13th day of March, 1968

My commission expires May 10, 1970

L. M. WHITING Notary Public.



15-135-20120-0000
ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY
705 4th National Bank Bldg.
Wichita, Kansas

Rotary Drilling Commenced 2/23/68

Rotary Drilling Completed 3/4/68

LOCATION: Harkness "C" No. 1, C SW SW Section 26-20S-23W, Ness County, Kansas.

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (13 jts.) 8 5/8" surface casing set at 270', cemented with 175 sacks cement. Circulated. Completed 3:00 PM February 23, 1968. No oil string run. D & A

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

95	Sand	C. F. S.
270	Hard Cement	<u>4255</u>
784	Shale & Shells	4270
794	Blaine	4290
871	Shale & Shells	4310
1085	Sand	4325
1409	Shale & Shells	4331
1452	Anhydrite	4340
1900	Shale & Shells	4348
2380	Lime & Shale	4360
2740	Lime	4370
4000	Lime & Shale	
4065	Lime	
4305	Lime & Shale	<u>Slope Tests</u>
4331	Lime & Chert	2000
4370	Mississippi - TD	2500
		3000
		3500
		4000

S. L. M.
4124

RECEIVED
STATE CORPORATION COMMISSION
MAR 18 1968
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By *C. W. Sebits*
C. W. SEBITS Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 11th day of March, 1968, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: May 10, 1970

L. M. Whitting
L. M. WHITTING Notary Public