


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County, Sec. 24 Twp. 20 Rge. 23 E/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines
150' SE/C/NW/NE
Lease Owner Mull Drilling Co., Inc.
Lease Name Whitley Well No. 4
Office Address 415 Page Court, 220 W. Douglas, Wichita, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced March 10 1978
Plugging completed March 21 1978
Reason for abandonment of well or producing formation
Depleted
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 4356'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|----------|------|----|--------|--------|------------|
| | 03-27-78 | | | 8 5/8" | 285' | none |
| | | | | 4 1/2" | 4345' | 2,417.57' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Dumped sand to 4300' and 5 sacks cement.
Shot casing at 3800', 3700', 3500', 3000', 2800', 2540', and 2450'.
Pulled 82 joints of 4 1/2" casing.
Squeezed well with 25 sacks of gel with 1 sack hulls and 140 sacks of cement.
Final pumping pressure 300 psi.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF Kansas COUNTY OF Barton, ss.
James W. Rockhold (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
P. O. Box 698, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 24 day of March, 1978

My commission expires ANITA L. BOGLE
Barton County, Kansas
My Appt. Exp. 21, 1981

Anita L. Bogle
Notary Public.

DRILLERS LOG

COMPANY: Mull Drilling Company, Inc.
 415 Page Court.
 Wichita, Kansas 67202

LEASE NAME: #4 Whitley
 150' SE of C NW NE
 Sec 24-20-23W
 Ness County, Kansas

CONTRACTOR: Slawson Drilling Company
 408 One Twenty Building
 Wichita, Kansas 67202

TOTAL DEPTH: 4356'

COMMENCED: December 16, 1975

COMPLETED: December 24, 1975

CASING: 278.76' set, at 285' w/200 sx 60/40 Poz

| | |
|----------------|---------------------|
| 0' to 289' | Surface Hole (12½") |
| 289' to 1422' | Blue Shale and Sand |
| 1422' to 2240' | Shale and Shells |
| 2240' to 3738' | Shale and Lime |
| 3738' to 4232' | Lime |
| 4232' to 4328' | Lime and Shale |
| 4328' to 4356' | Miss |
| 4356' | RTD |

FEB 1976

STATE OF KANSAS
 COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc. upon oath state that the above and foregoing is a true and correct copy of the log of the #4 Whitley.

James C. Remsberg
 James C. Remsberg, Vice-President

Subscribed and sworn to me on December 31, 1975.

Dolores B. Coady
 Dolores B. Coady, Notary Public

My Commission expires:

