

State of Kansas



15-159-20548-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

6-25-75 JUN 25 1975

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Lavern Brown of Parrish Oil Company has this
date requested permission to plug the following described well:Mr. Brown guarantees payment of the plugging fee.Operator's full Name: Parrish Oil CompanyComplete Address: 714 4th National Bldg., Wichita, Kansas 67202Lease Name: PFister Well No. 1Location: NE SE NE Sec. 10 Twp. 21 Rge. 10 (W) XCounty: Rice Total Depth 3386 Oil WellGas Well Input Well SWD Well D & A X Lost Hole Mr. Brown was instructed to plug the well as follows:

Fill hole with mud. Push plug to 450' and pump 40
sacks cement through drill pipe at 450'. Pump 25
sacks cement through drill pipe at 180'. Push plug
and 1/2 sack hulls to 46' and cap hole with 10 sacks
Cement. Bridge rat hole and cement with 2 sacks cement.

Very truly yours,

Conservation Division Agent