



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
APR 19 1971  
CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Odin of Red Tiger Drilling has this

date requested permission to plug the following described well:

Mr. Odin guarantees payment of the plugging fee.

Operator's full Name: Frontier Oil Co.

Complete Address: 1720 Wichita Plaza Wichita, Ks.

Lease Name: Bartel Well No. 1

Location: G W/2 NE Sec. 18 Twp. 17 Rge. (E)(W) 16

County: Rush Total Depth 3676' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Odin was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 420' and displace

50 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and

displace 25 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of collar.

Very truly yours,

Eric J. Messing  
Conservation Division Agent