

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAY 2 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jones of Cities Service has this

date requested permission to plug the following described well:

Mr. Jones guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Co.

Complete Address: 710 Sutton Place Wichita, Ks.

Lease Name: Kanaga Well No. 1

Location: C SW NE Sec. 9 Twp. 20 Rge. (E)(W) 23

County: Ness Total Depth 4470' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Jones was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 535' and displace

50 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and

displace 25 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo F. Mearns
Conservation Division Agent