

State of Kansas



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 17 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Burton of Pickrell Drlg. has this date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company

Complete Address: 705 4th Nat'l Bank Bldg., Wichita, Ks.

Lease Name: Ripple "A" Well No. 1

Location: CSE SW Sec. 12 Twp. 20 Rge. 23 (E)(W) X

County: Ness Total Depth 4375 Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Burton was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace  
70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and  
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sk hulls and 10 sk cmt to base of cellar. Plug rat hole with  
2 sk cmt.

Very truly yours,

Leo F. Messer  
Conservation Division Agent