

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)RECEIVED  
STATE CORPORATION COMMISSION  
FEB 5 1970  
CONSERVATION DIVISION  
Wichita, KansasJ. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Steincamp of Strata Drlg. has this

date requested permission to plug the following described well:

Mr. Steincamp guarantees payment of the plugging fee.Operator's full Name: R. V. LehnerComplete Address: Box 398 Ness City, KansasLease Name: Strobel Well No. 4Location: C SE SW Sec. 19 Twp. 20 Rge. (E)(W) 23County: Ness Total Depth 4388 Oil Well Gas Well  Input Well  SWD Well  D & A XX Lost Hole Mr. Steincamp was instructed to plug the well as follows:Gun pits, circulate heavy mud, set cementing plug at 660' and displace70 sk cmt thru drill pipe. Heavy mud to 270' set cementing plug anddisplace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementingplug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

  
Conservation Division Agent