


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report for  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Greeley County, Sec. 5 Twp. 19S Rge. (E)40 (W)  
Location as "NE/CNW/SW" or footage from lines NW SE  
Lease Own: Publishers Petroleum  
Lease Name Kelly Unit Well No. 1  
Office Address 500 N. Broadway Okla. City, Okla.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 2/24/ 1963  
Application for plugging filed 10/23/ 1963  
Application for plugging approved Verbal 19  
Plugging commenced 10/11/ 1963  
Plugging completed 10/14/ 1963  
Reason for abandonment of well or producing formation not commercially  
Productive

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production ----- 19 ---  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
All formations dry				8 5/8	174'	none
See attached log				4 1/2	2940'	1608'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pumped ten sacks of cement to plug off bottom perforations (cement from 2833' to T. D.)

Mud from 2833' to 217' and pumped 25 sacks cement at 217. (cement from 217' to 137')

Mud from 137' to 35' and 5' rock bridge. 10 sacks cement at 30' to base of cellar.

completed plugging 10/14/63

Cut surface casing off 3' below ground level and weld cap of same

RECEIVED  
STATE CORPORATION COMMISSION

OCT 28 1963  
10-28-63  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargent's Casing Pulling Service  
Address 121 W. 9th St. Liberal, Kansas

STATE OF Kansas COUNTY OF Seward, ss.

Edward W. Jackson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Edward W. Jackson  
1411 N. Coulter, Liberal, Kan  
(Address)

SUBSCRIBED AND SWORN TO before me this 26 day of October, 1963

Albert S. Swank  
Notary Public.

My commission expires 11-23-66

15-071-19001-0000

LEASE: KELLY UNIT WELL NO. 1  
OWNER: PUBLISHERS PETROLEUM  
CONTRACTOR: EARL F. WAKEFIELD  
COMM: 2-13-63 COMP: 2-17-63

LOCATION: NW SE  
SECTION 5-19S-40W  
GREELEY COUNTY, KANSAS  
CASING: 8 5/8" Set at 174'  
4 1/2" Set at 2940'

Surface Soil	50
Sand and Clay	155
Blue Shale	175
Shale and Shells	1125
Sand and Shale	1220
Shale and Shells	1415
Shale, Shells, Red Bed	1825
Red Bed, Shale and Shells	2262
Shale and Shells	2487
Shale - Shells	2520
Anhydrite - Shale	2635
Shale	2835
Shale and Lime	2935
Shale and Lime	2940
T.D.	2940

RECEIVED  
STATE CORPORATION COMMISSION

OCT 28 1963

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS        )  
                              ) SS  
COUNTY OF SEDGWICK )

I hereby certify that the above is a true and correct copy of the log on the KELLY UNIT WELL NO. 1, located NW SE Section 5-19S-40W, Greeley County, Kansas.

EARL F. WAKEFIELD

By Earl F. Wakefield

Subscribed and sworn before me this 28th day of February, 1963.

My commission expires:  
January 25, 1965

Wanda W. Riley  
WANDA W. RILEY                      NOTARY