

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15071-26271-0000

LEASE NAME Greeley Lands Inc.

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

SPOT LOCATION NW NW NE

SEC 31 TWP 17 SRGE 41 ~~40~~ or (W)

COUNTY Greeley

Date Well Completed 12-23-82

Plugging Commenced 3-36-86

Plugging Completed 3-26-86

LEASE OPERATOR Texaco Inc.

ADDRESS Box 2420, Tulsa, Ok

PHONE # (918) 560-6205 OPERATORS LICENSE NO. 5153

Character of Well Dry
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist #1 - Dodge City, Ks

Is ACO-1 filed? Yes If not, is well log attached? Not Available

Producing formation None Depth to top Completed as ASD bottom T.D. 5850

Show depth and thickness of all water, oil and gas formations. PB 3300'

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8	608'	None
				5-1/2	5850	1417'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Well plugged from 3300-3034' w/mud; 3403-2850' w/20 sx cmt - 1 sx hulls; from 2850'-1400' w/mud; from 1400-1300' w/50 sx cmt; from 1300-650' w/mud; from 650-550' w/50 sx cmt; from 550-40' w/mud; from 40'-3' w/10 sx cmt; 3'-0 w/dirt; welded on steel plate.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling License No. 6547
Address Box 506, Liberal, Kansas

STATE OF Oklahoma COUNTY OF Tulsa, ss.

R. W. Blohm, Ass't District Manager (employee of operator) XXX
(~~operator~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. W. Blohm
R. W. BLOHM
(Address) Box 2420, Tulsa, Ok 74102

SUBSCRIBED AND SWORN TO before me this 7th day of July, 1986

Deborah M. Coburn
Notary Public
STATE CORPORATION COMMISSION
1111 - 9 1986
CONSERVATION DIVISION

My Commission expires: 8-3-88

OCT 04 1982

15-071-20271-0000

WELL LOG


COMPANY Texaco, Inc.
FARM Greeley Lands, Inc. NO. 1

SEC. 21 T. 17S R. 14W
LOC. 2400 FEL 330 FNL

TOTAL DEPTH 5850 RTD
COMM. 9-1-82 COMP. 9-17-82

COUNTY Greeley, Kansas

CONTRACTOR DaMac Drilling Inc.
CASING 8 5/8 set @ 400



ELEVATION

PRODUCTION 5 1/2 set @ 5849

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand, RedBed	0	608
RedBed, Clay	608	760
Clay, Lime, Shale	760	1853
Lime, Shale	1853	5850

RECEIVED
STATE CORPORATIONS COMMISSION


JAN 06 1983

LICENSING DIVISION
Wichita, Kansas

State of Kansas }
County of Barton } ss

I, Martha J. McKown of DaMac Drilling Inc.

upon oath state the above and foregoing is a true and correct copy of the log of the Greeley Lands No. 1 well.



Martha J. McKown

Subscribed and sworn to before me this 17th day of Sept. 1982

My Commission Expires: _____

Vada I. Sullivan

NOTARY PUBLIC