

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-071-20,022-0000

LEASE NAME Bounds

WELL NUMBER 1

SPOT LOCATION C-NW

SEC. 13 TWP. 20 RGE. 40 (E or W)

COUNTY Greely

Date Well Completed 4-7-73

Plugging Commenced 11-24-1989

Plugging Completed 11-28-1989

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Dernick Resources Inc.

ADDRESS One Commerce Green - 515 W. Green Rd., Suite 1150  
Houston, TX 77067

PHONE # (713) 873-6883 OPERATORS LICENSE NO. 7040

Character of Well gas  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing formation ~~Arider~~ WINFIELD Depth to top 2800 bottom 2820 T.O. 2948'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8"	350'	0'
Production				4 1/2"	2948'	1420'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pump 2 sacks hulls and 20 sks. cement to 2700'  
Pressured to 400 lbs. - Mud 2700' to 1350' - Pump 50 sks. cement 1350' to 1200'  
Mud 1200' to 380' - pump 40 sks. cement 380' to 260' - Mud 260' to 40'  
Put bridge and 10 sks. 40' to 3', cut off 8 5/8", 3' below ground level and cap.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor MIDWEST CASING PULLING SERVICE License No. 6497  
Address Box F, Sublette, Ks. 67877

STATE OF KANSAS COUNTY OF HASKELL, ss.

I, Edgar J. Eves

~~Operator~~ (employee of operator) or  
operator of above-described well, being first duly sworn on oath, says: That  
I have knowledge of the facts, statements, and matters herein contained and  
the log of the above-described well as filed that the same are true and  
correct, so help me God.

  
SONDRA L. EVES  
Haskell County, Ks.  
My App. Exp. 12-6-92

(Signature) Edgar J. Eves  
(Address) Box F, Sublette, Ks. 67877

SUBSCRIBED AND SWORN TO before me this 1st day of Dec., 1989

Sondra L. Eves  
Notary Public

My Commission expires: 12-6-92

RECEIVED  
12-11-89  
CONSERVATION DIVISION  
Wichita, Kansas