

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-071-20078-0000

LEASE NAME Coupland

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 3

 Ft. from S Section Line

 Ft. from E Section Line

9-30-97

LEASE OPERATOR Horseshoe Operating, Inc.

SEC. 26 TWP. 20 RGE. 40(E) or (W)

ADDRESS 500 W. Texas, Suite 1190 Midland, Tx 79701 COUNTY Greeley

PHONE (915) 683-1448 OPERATORS LICENSE NO. 4894

Date Well Completed 6/18/75

Character of Well Gas

Plugging Commenced 6/97

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

Plugging Completed 8/97

The plugging proposal was approved on 3/7/97 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? no (was previously sent in)

Producing Formation Winfield Depth to Top 2827 Bottom 2835 T.D. 2855

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Winfield	Gas - Water	0.	232	8-5/8	232	
2827-2835						
		0.	2855	4-1/2	2855'	801

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set

See attached sheet

Name of Plugging Contractor Allied Cementing License No.

Address Box 31 Russel, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Horseshoe Operating, Inc.

STATE OF Texas COUNTY OF Midland, ss.

Horseshoe Operating, Inc. (Employee of Operator) or (Operator) o

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Debbie Franklin

(Address) 500 W. Texas, Suite 1190

SUBSCRIBED AND SWORN TO before me this 26 day of September, 19 97

 Lottie Arnold
Notary Public

LOTIE ARNOLD
MY COMMISSION EXPIRES
December 4, 1998

Expires: 12/4/98

HORSESHOE OPERATING, INC.
OIL AND GAS

500 West Texas, Suite 1190 • Midland, Texas 79701 • (915) 683-1448 FAX (915) 686-9449

September 26, 1997

Well Plugging Record

15-071-20078-0000
Coupland #3
Sec. 26-20-40
Greeley Co., Kansas

Set bottom plug in 4-1/2" casing - using 25 sxs 60/40 poz mix w/6% gel, 100# cottonseed hulls. Pressure 4-1/2" casing to 300#.

Perforate 4-1/2" @ 1350'. Pump 80 sxs cement. Shot off 4-1/2" casing @ 800'. Pull up to 659'. Pump 50 sxs cement. Pull up to 250'. Pump 50 sxs. Pull up 40'. Pump 40 sxs cement. All cement 60/40 poz w/6% gel.

2000-09-26 15:07:20
15-071-20078-0000
Coupland #3
Sec. 26-20-40
Greeley Co., Kansas