


STATE OF KANSAS
CONSERVATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Greely County, Sec. ²⁴ 28 Twp. 20 Rge. 10 (E) (W) X
Location as "NE/CNW/SE/NE" or footage from lines 1980 ft. from NE/W lines
Lease Owner Hughes Seewald
Lease Name Watson Well No. 1
Office Address 701 1st. Natl. Bk. Bldg. Amarillo, Texas 79101
Character of Well (completed as Oil, Gas or Dry Hole) ~~Gas~~ Dry
Date well completed 19__
Application for plugging filed 19__
Application for plugging approved April 16, 1975 19__
Plugging commenced 1-28 1975
Plugging completed 1-30 1975
Reason for abandonment of well or producing formation dry hole
If a producing well is abandoned, date of last production 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2810
Show depth and thickness of all water, oil and gas formations

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	375	none
				4 1/2	2836	1932

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pump 2 sks. of hulls & 10 sks of cement to 2600
Pump 35 sks. of cement from 800 to 700
Pump 35 sks. of cement from 375 to 275
put Bridge & 10 sks. of cement from 40 to 0

JUN 11 1975
6-9-75

Name of Plugging Contractor Sargeants Casing Pulling Service Kansas No. 511
Address Box 506 Liberal, Kansas 67901

STATE OF Texas COUNTY OF Potter ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Hughes Seewald
701 First Nat'l Bank Bldg. Amarillo, Tex 79101
(Address)

Subscribed and sworn to before me this 5th day of June 1975

My commission expires 6-1-77 Notary Public.

KANSAS DRILLERS LOG

IMPORTANT
 Kans. Geo. Survey request
 samples on this well.

S. 24 T. 20 R. 40 W


API No. 15 — 071 — 20,041-0000
 County Number

Loc. C SE NW

Operator
Hughes Seeward
 Address 701 First National Bank Building
Amarillo, Texas

County Greeley

Well No. #1 Lease Name Watson



Footage Location
1980 feet from (N) line 1980 feet from (W) line

Principal Contractor Sterling Drilling Co. Geologist Ralph M. Reynolds

Spud Date June 7, 1973 Total Depth 2840 P.B.T.D.

Elev.: Gr. 3534

Date Completed - Oil Purchaser -

DF KB 3544

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/2"	8-5/8"	28#	363'	Quickset	374	3% CC
Production	7-7/8"	4 1/2"	10.5#	2846'	Polmix	200	2% gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
none					
TUBING RECORD			2/ft	jets	2814-20
Size	Setting depth	Packer set at			
2-3/8	2830	none			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
228 bbls H ₂ O 12,000# sand	2814-20
RECEIVED STATE CORPORATION COMMISSION APR 16 1975	

INITIAL PRODUCTION DIVISION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	CFPB
	bbls.	MCF	125 BPD	bbls.	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Hughes Seewald

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No.

1

Lease Name

Watson

Dry Hole

S 26 T 20S R 40 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
None			Accoustilog	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Hughes Seewald
Signature

Operator

Title

April 9, 1975

Date