

To: 1 070003
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 137-00599-0000 Not Available

C. NW 28 SEC. 21 T. 18S, R. 24W/R
4620 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8759

Lease Name Leikam Well # 1

Operator: Mack Energy Co.
Name & Address 1202 N. 10th Street
Duncan, OK 73533

County Ness 142.68
Well Total Depth 4390 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 269

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 24 Month: June Year: 19 85

Plugging proposal received from Ron Hoover

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4388' PBTD 4378' Perfs at 4328-34'

1st plug sand back to 4270' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 70 sx cement, 15 sx gel, 1 sack hulls, and 125 sx cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:20 pm Day: 24 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4270' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 70 sx cement, 15 sx gel, 1 sack hulls and 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Maximum pressure 500 psi and shut in 200 psi

JUL 01 1985
7-1-85
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Recovered 2532' 4 1/2" casing. Used 60/40 Pozmix 6% gel.

(If additional description is necessary, use BACK of this form.)

did ~~not~~ observe this plugging.

INVOICED
DATE 7-10-85
INV. NO. 8822

Signed Dan Goodner
(TECHNICIAN)