

1 030991

11-9
API NUMBER 15-135-23,303-0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

Appr. SE SE NE SEC. 28, T 18 S, R 24 W/8

3194 feet from S section line
554 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3919

Lease Name Cranston Well # 1

Operator: Challenger Exploration

County Ness 142.84

Name & Address

P.O. Box 1112
Hays, KS 67601

Well Total Depth 4395 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 237

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 1 a.m. Day: 9 Month: 11 Year: 19 88

Plugging proposal received from Lloyd Delett

(company name) Murfin Drilling Company (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2289' Anhydrite 1605-1626'

1st plug at 1620' with 50 sx cement, 2nd plug at 840' with 80 sx cement,
3rd plug at 260' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4 a.m. Day: 9 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1620' with 50 sx cement,

2nd plug at 840' with 80 sx cement,

3rd plug at 260' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

NOV 14 1988

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

INVOICED If not observe this plugging.

DATE 11-21-88

Signed Steve Durrant (TECHNICIAN)

INV. NO. 23034

11-9

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date: 11 01 88 month day year

API Number 15-135-23,303-0000 2

OPERATOR: License # 3919 Name Challenger Exploration Address P. O. Box 1112 City/State/Zip Hays, KS 67601 Contact Person Vince Werth Phone 913-628-2685

APPR C SE SE NE 28 18 24 Sec. Twp. S, Rg. East West Ft. from South Line of Section Ft. from East Line of Section

CONTRACTOR: License # 6033 Name Murfin Drilling Company City/State Wichita, KS 67202

(Note: Locate well on Section Plat on reverse side) Nearest lease or unit boundary line 330 feet County Ness Lease Name Cranston Well # 1 Ground surface elevation 2289 feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Depth to bottom of fresh water 100 Depth to bottom of usable water 500 800' Surface pipe by Alternate: 1 2 X Surface pipe planned to be set 300 Conductor pipe required N/A Projected Total Depth 4400 feet Formation Miss.

Well Drilled For: Well Class: Type Equipment: X Oil Storage Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

IF OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 10-20-88 Signature of Operator or Agent Jack Goss, Agent for Operator Title Drilling Manager

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. X (2) This Authorization Expires 4-24-89 Approved By Ret. 10-24-88

EFFECTIVE DATE: 10-29-88 SPUD 10-2-88

C SE SE NE 28 18 24 Sec. Twp. S, Rg. East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with columns for plug depth, formation, and feet of material. Includes notes for Rathole to surface minus 5 feet and Mousehole to surface minus 5 feet.

NOTE: Agreement between

Handwritten log entries: PUSHED Lloyd De 1st, TD 4395, SURFACE PIPE 8 7/8 @ 237, ANHYDRITE 1605 ELEVATION 2289, STARTING TIME & DATE 1:00 AM 11-9-88, COMPLETION TIME & DATE 4:00 AM 11-9-88, 1st PLUG @ 1620 FT. W/ 50 SX, 2nd PLUG @ 840 FT. W/ 50 SX, 3rd PLUG @ 260 FT. W/ 40 SX, 4th PLUG @ 40-0 FT. W/ 10 SX, RAT HOLE CIRCULATED W/ 15 SX, MOUSE HOLE CIRCULATED W/ SX, WATER WELL PLUGGED W/ SX, CEMENT COMPANY 60/40 606, TECHNICIAN S&D

RECEIVED STATE CORPORATION COMMISSION NOV 14 1988 CONSERVATION DIVISION Wichita, Kansas