

1090963

TO: STATE CORPORATION COMMISSION

10-28

API NUMBER 15-135-24,062-0000  
20'N 70'W OF W/2 NW SEC. 28, T 18 S, R 24 W

CONSERVATION DIVISION - PLUGGING SECTION 1300 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 590 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME STOECKLEIN WELL # 1-28

TECHNICIAN'S PLUGGING REPORT COUNTY NESS 143.33

OPERATOR LICENSE # 31930 WELL TOTAL DEPTH 4410 FEET

OPERATOR: BLUERIDGE PETROLEUM CORP PRODUCTION CSG: SIZE " FEET

NAME AND PO BOX 385 SURFACE CASING: SIZE 8 5/8 " FEET 214'

ADDRESS NESS CITY, KS 67560

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR DISCOVERY DRILLING, INC LICENSE NUMBER 31548

ADDRESS PO BOX 763, HAYS, KS 67601

COMPANY TO PLUG AT: HOUR: 5:30 PM DAY: 28 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM TOM

(COMPANY NAME) DISCOVERY DRILLING, INC (PHONE) 785-623-2920

WERE:

1ST PLUG AT 1620' WITH 50 SX CEMENT, 2ND PLUG AT 950' WITH 80 SX CEMENT,

3RD PLUG AT 230' WITH 40 SX CEMENT, 4TH PLUG AT 40' WITH 10 SX CEMENT,

5TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CEMENT,

6TH PLUG TO CIRCULATE MOUSEHOLE WITH 10 SX CEMENT

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 7:45 PM DAY: 28 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 1620' WITH 50 SX CEMENT, 2ND PLUG AT 950' WITH 80 SX CEMENT,

3RD PLUG AT 230' WITH 40 SX CEMENT, 4TH PLUG AT 40' WITH 10 SX CEMENT,

5TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CEMENT,

6TH PLUG TO CIRCULATE MOUSEHOLE WITH 10 SX CEMENT

REMARKS: USED 60/40 POZMIX 6% GEL 3/4# FLO SEAL BY ALLIED  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING.

SIGNED [Signature] (TECHNICIAN) FORM CP-2/3 [Signature]

11-4-98  
60252

11-3-98