

15.001.03297.00.00/04
7-6
R

3 020695

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Operator: State of Kansas

Name: Fee Fund Plugging

Address:

API NUMBER

SE/4, SEC. 7, T. 26 S. R. 18 W/E

1400 feet from S section line

800 feet from E section line

Lease Name Mathias (Tucker) Well # OW 6

County Allen

Well Total Depth Approx. 850 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 feet N/A

Abandoned Oil Well Gas Well Input Well X SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor K.W. Oil Well Service License Number 8933

Address P.O. Box 15, Thayer, Kansas 66776

Company to plug at: Hour: 12:00 pm Day: 8 Month: 6 Year: 1990

Plugging proposal received from Clayton Titel

(company name) KCC (phone) 316-431-6946

were: This well consisted of 2" casing to approximately 800' that had evidently been

cemented in from TD to 75' 3/4" tubing on a concentric packer was set at 75'. The

plugging proposal was to pull the 3/4" tubing, drive the rest of the packer to as

deep a depth as possible, and circulate as much of the 2" as possible full of cement.

Plugging Proposal Received by Clayton P. Titel
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 4:45 pm Day: 6 Month: 7 Year: 1990

ACTUAL PLUGGING REPORT The 3/4" tubing was removed. The remains of the packer were

driven to 500'. 1" pipe was ran to 500' inside the 2" casing. Cement was pumped

into the 1" pipe until cement circulated from the 1" and 2" annulus at surface. 1"

pipe was ran to 75' in the 2" and 8" annulus. The 2" and 8" annulus was circulated

full of cement from 75' to surface. All 1" pipe was removed. The 8" surface

casing was capped, squeezed to 50 PSI and 28 sacks of cement were pumped

Remarks: into this well by Consolidated Oil Well Services, Inc.
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed Clayton P. Titel
(TECHNICIAN)