

3 020694

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Operator: State of Kansas

Name &
Address Fee Fund Plugging

API NUMBER _____

SE/4, SEC. 7, T 26 S. R. 18 XWXE

1450 feet from S section line

600 feet from E section line

Lease Name Mathias (Tucker) Well # OW 7

County Allen

Well Total Depth Approx. 850 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 5 feet N/A

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor K.W. Oil Well Service License Number 8933

Address P.O. Box 15, Thayer, Kansas 66776

Company to plug at: Hour: 8:00 am Day: 8 Month: 6 Year: 19 90

Plugging proposal received from Clayton Titel

(company name) KCC (phone) 316-431-6946

were: This well consisted of 2" casing to approximately 800' that had evidently been

cemented in from bottom to top. 3/4" tubing probably, on a concentric packer, was set

at an unknown depth in this well. The plugging proposal was to remove as much

3/4" as possible and fill as much of the well as possible with cement.

Plugging Proposal Received by Clayton P. Titel
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 2:30 pm Day: 6 Month: 7 Year: 1990

ACTUAL PLUGGING REPORT 310' of 3/4" tubing were removed from this well. The packer,

set at an unknown depth, and 3/4" tubing from that depth to 310' were left in the well.

3/4" pipe was ran to 310'. Cement was pumped into the 3/4" pipe until cement circulated

from the 2" and 3/4" annulus at surface. The 310' of 3/4" were then removed. 5 more sacks

of cement were squeezed into the well. The well was shut in at 500 PSI. 10 sacks

of cement total were pumped into this well by Consolidated Oil Well Services Inc.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

I (did / ~~XXXXXX~~) observe this plugging.

Signed Clayton P. Titel
(TECHNICIAN)