

15-001-01136-00-00

API NUMBER 15- CONTROL #20000002-004

NE, SEC. 17, T 26 S, R 18 E

3712 FEET FROM SOUTH SECTION LINE

1405 FEET FROM EAST SECTION LINE

LEASE MCKINLEY/MCCARTNEY WELL # 4

COUNTY ALLEN

WELL TOTAL DEPTH APPROX. 800' FEET

PRODUCTION CSG: SIZE	FEET
----------------------	------

SURFACE CASING: SIZE 8 FEET N/A

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SWD WELL _____ D/A _____

PLUGGING CONTRACTOR SPLANE PULLING & ROUSTABOUT SERVICE LICENSE NUMBER 10312

COMPANY TO PLUG AT: HOUR: 8:00AM DAY: 9 MONTH: 2 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL

(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-432-2300

WERE: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 800' THAT HAD BEEN CEMENTED
IN AT TD ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE
FULL OF CEMENT.

PLUGGING PROPOSAL RECEIVED BY C.P. TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL _____ PART _____ X _____ NONE _____

OPERATIONS COMPLETED: HOUR: 1:00 PM DAY: 9 MONTH: 2 YEAR: 2000

ACTUAL PLUGGING REPORT 3/4" PIPE WAS RAN INTO THE 2" CASING TO 693'. CEMENT WAS

PUMPED INTO THE 3/4" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE

3/4" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUS TO 500'. CEMENT WAS

PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 8" SURFACE CASING AT SURFACE.

1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

RECEIVED
STATE CORPORATION COMMISSION

REMARKS:

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.) CONSERVATION DIVISION
Wichita, Kansas

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED

(TECHNICIAN)

FORM CP-2/3

