

TO:

CONSERVATION DIVISION - PLUGGING SECTION

WICHITA STATE OFFICE BLDG., 130 S. MARKET

WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 101

OPERATOR: STATE OF KANSAS

NAME AND	FEE FUND PLUGGING
----------	-------------------

ADDRESS

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SPLANE PULLING & ROUSTABOUT SERVICE LICENSE NUMBER 6372

ADDRESS P.O. BOX 386, CHANUTE, KS 66720

COMPANY TO PLUG AT: HOUR: 8:00AM DAY: 21 MONTH: 1 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM CLAYTON TITEL

(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-432-2300

WERE: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 800' THAT HAD BEEN CEMENTED
IN AT TD ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE
FULL OF CEMENT.

PLUGGING PROPOSAL RECEIVED BY C.P. TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL _____ PART X _____ NONE _____

OPERATIONS COMPLETED: HOUR: 1:00PM DAY: 25 MONTH: 1 YEAR: 2000

ACTUAL PLUGGING REPORT 3/4" PIPE WAS RAN INTO THE 2" CASING TO 756'. CEMENT WAS

PUMPED INTO THE 3/4" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE

3/4" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUS TO 550'. CEMENT

WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING RECEIVED

SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

FFB - 2 2000

REMARKS: _____ CONSERVATION DIVISION

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM) Wichita, Kansas

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED

(TECHNICIAN)

FORM CP-2/3