

3021791

15-001-01140-00-00

TO:

API NUMBER 15- CONTROL #20000002-024

STATE CORPORATION COMMISSION

NE, SEC. 17, T 26 S, R 18 E

CONSERVATION DIVISION - PLUGGING SECTION

4039 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET

1746 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE MCKINLEY/MCCARTNEY WELL # 24

TECHNICIAN'S PLUGGING REPORT

COUNTY ALLEN

OPERATOR LICENSE # 101

WELL TOTAL DEPTH APPROX. 800' FEET

OPERATOR: STATE OF KANSAS

PRODUCTION CSG: SIZE FEET

NAME AND FEE FUND PLUGGING

SURFACE CASING: SIZE 8 FEET N/A

ADDRESS

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SPLANE PULLING & ROUSTABOUT SERVICE LICENSE NUMBER 6372

ADDRESS P.O. BOX 386, CHANUTE, KS 66720

COMPANY TO PLUG AT: HOUR: 8:00AM DAY: 10 MONTH: 2 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL

(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-432-2300

WERE: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 800' THAT HAD BEEN CEMENTED
IN AT TD ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE
FULL OF CEMENT.

PLUGGING PROPOSAL RECEIVED BY C.P. TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART X NONE

OPERATIONS COMPLETED: HOUR: 12:30PM DAY: 10 MONTH: 2 YEAR: 2000

ACTUAL PLUGGING REPORT 3/4" PIPE WAS RAN INTO THE 2" CASING TO 735'. CEMENT WAS

PUMPED INTO THE 3/4" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE

3/4" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUS TO 550'. CEMENT WAS

PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 8" SURFACE CASING AT SURFACE.

1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

RECEIVED
STATE CORPORATION COMMISSION

REMARKS:

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.) CONSERVATION DIVISION
Wichita, Kansas

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED

Clayton P. Titel
(TECHNICIAN)

FORM CP-2/3

FEB 23 2000