

3021732

15-001-01113-0000

TO:

API NUMBER 15- CONTROL #20000002-030

STATE CORPORATION COMMISSION

NW, SEC. 17, T 26 S, R 18 E

CONSERVATION DIVISION - PLUGGING SECTION

3890 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET

3455 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE MCKINLEY/MCCARTNEY WELL # 30

TECHNICIAN'S PLUGGING REPORT

COUNTY ALLEN

OPERATOR LICENSE #

101

WELL TOTAL DEPTH APPROX. 800 FEET

OPERATOR: STATE OF KANSAS

PRODUCTION CSG: SIZE FEET

NAME AND FEE FUND PLUGGING

SURFACE CASING: SIZE 8" FEET N/A

ADDRESS

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SPLANE PULLING & ROUSTABOUT SERVICE LICENSE NUMBER 6372

ADDRESS P.O. BOX 386, CHANUTE, KS 66720

COMPANY TO PLUG AT: HOUR: 8:00AM DAY: 27 MONTH: 12 YEAR: 99

PLUGGING PROPOSAL RECEIVED FROM CLAYTON TITEL

(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-432-2300

WERE: THIS WELL CONSISTED OF 2" CEMENT LINED CASING TO APPROXIMATELY 800' THAT HAD
BEEN CEMENTED IN AT TD ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE
WELL AS POSSIBLE FULL OF CEMENT INSIDE AND OUTSIDE THE 2" CASING.

PLUGGING PROPOSAL RECEIVED BY C.P. TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART X NONE

OPERATIONS COMPLETED: HOUR: 1:00 PM DAY: 27 MONTH: 12 YEAR: 99

ACTUAL PLUGGING REPORT 3/4" PIPE WAS RAN INTO THE 2" CASING TO 675'. CEMENT WAS

PUMPED INTO THE 3/4" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE

3/4" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUS TO 550'. CEMENT WAS

PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 8" SURFACE CASING AT SURFACE.

THE 1" PIPE WAS REMOVED. SETTLAGE AND DISPLACEMENT WERE FILLED FROM SURFACE.

REMARKS:

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED

Clayton P. Titel
(TECHNICIAN)RECEIVED
STATE CORPORATION COMMISSION

JAN 07 2000

CONSERVATION DIVISION
FORM 67-293
Kansas