

3 021848

15-001-01190 00-00

To:

API NUMBER

CONTROL NO. 20000002 - 055

STATE CORPORATION COMMISSION

NE 14

Sec/Twp/Rge S.17-T26-R18E

Wichita State Office Bldg. - PLUGGING SECTION

3861 feet from south section line

130 S. Market, Room 2078

1899 feet from east section line

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Lease/Well#

MCKINLEY/MCARTNEY NO.55

Operator License #

101

County

ALLEN

Operator: STATE OF KANSAS

Well Total Depth 800'

feet

Name & FEE FUND PLUGGING

Production Pipe: 11/2"

Size Feet 800'

Address

Surface Casing: 10"

Size Feet

AB oil well Gas Well

SWD Well/ Input Well

E-3435

D & A

Other well as hereinafter indicated:

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICE

Lic. #

6372

Address: P.O. BOX 386, CHANUTE, KANSAS 66720

Company to plug at: Hour:

8:00A.M. Day:

18 Month:

4

2000

Plugging proposal received from CLAYTON P. TITEL

Company Name:

KANSAS CORPORATION COMMISSION

Phone:

316-432-2300

Were:

THIS WELL CONSISTED OF 1 1/2" CASING TO APPROXIMATELY 800' THAT HAD BEEN

CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE

WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent:

All

X

Part

TECHNICIAN

None

Operations Completed: Hour:

1:00 P.M. Day:

18 Month:

4

2000

Actual Plugging Report:

3/4" PIPE WAS FISHED FROM THE WELL TO 315'. NO MORE PIPE

COULD BE RETREIVED. 3/4" PIPE WAS RAN INTO THE 1 1/2" CASING TO 315'. CEMENT WAS PUMP

INTO THE 3/4" PIPE UNTIL CEMENT CIRCULATED FROM THE 1 1/2" CASING AT SURFACE. THE 3/4"

PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 1 1/2" AND 10" ANNULUS TO 475'. CEMENT WAS

PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 10" SURFACE CASING AT SU

THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

RECEIVED

STATE CORPORATION COMMISSION

Remarks:

(If additional description is necessary, use BACK of this form.)

APR 25 2000

1

DID

observe this plugging

Signed:

CONSERVATION DIVISION
Wichita, KansasClayton P. Titel
TECHNICIAN

R