



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. - 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Michaels of Sage Drlg. has this

date requested permission to plug the following described well:

Mr. Michaels guarantees payment of the plugging fee.

Operator's full Name: Monarch Oil & Gas Co.

Complete Address: 1429 Wichita Plaza Wichita, Ks,

Lease Name: Littler Well No. 1

Location: SE SW NW Sec. 28 Twp. 16 Rge. 19 (E)(W) X

County: Rush Total Depth 3860' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Michaels was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600' and displace

70 sc cement thru drill pipe. Heavy mud to 240' set cementing plug and

displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole

with 2 sc cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 1 1968

CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

Leo F. Messing
Conservation Division Agent