

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
JUL 13 1957
CONSERVATION DIVISION
WICHITA, KANSAS

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Millard of Red Tiger Drlg. has this date requested permission to plug the following described well:

Mr. Millard guarantees payment of the plugging fee.

Operator's full Name: Frontier Oil Co.

Complete Address: 1720 Kansas State Bank Bldg., Wichita, Ks.

Lease Name: Schneider "C" Well No. 1

Location: SW SW SE Sec. 30 Twp. 16 Rge. (E)(W) 19

County: Rush Total Depth 3866' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Millard was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 50 sk cmt plug at 500' thru drill

pipe. Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo Massey
Conservation Division Agent