



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

12-20-74

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Lahar of B & B Drlg. has this

date requested permission to plug the following described well:

Mr. Lahar guarantees payment of the plugging fee.

Operator's full Name: L & L Oil Co., & Jones & Fellow Oil Co.

Complete Address: 720 Union Center, Wichita, Ks.

Lease Name: Foster Well No. 1

Location: NE NW NE Sec. 9 Twp. 16 Rge. (E)(W) 20

County: Rush Total Depth 3975' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Lahar was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 75 sk cem plug at 800' thru drill  
pipe. Heavy mud to 225' set 25 sk cmt plug thru drill pipe. Heavy mud  
to 40' set solid bridge & 10 sk cmt to base of cellar.

Very truly yours,

Leo R. Massey  
Conservation Division Agent