

State of Kansas



GEORGE DOCKING Governor  
MARION BEATTY Chairman  
HARRY G. WILES Commissioner  
RICHARD C. BYRD Commissioner  
RAYMOND B. HARVEY Secretary  
CLYDE E. MILLIGAN Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS  
JEWEL M. OGDEN, Director

Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

I have this date 11-12-58, 1958, authorized the following plugging operation:

Operator's Full Name: Don. J. Pratt  
Complete Address: Hays, Kans  
Lease Name: Campbell Well No. 1  
Location: SW SW NE Sec. 21 Twp. 16 Rge. 20 (E) (W)  
County: Rush Total Depth: 4124  
Oil Well  Gas Well  Input Well  SWD Well  D & A   
Other well as hereafter indicated: \_\_\_\_\_

Operator was instructed to plug well as follows:

8 5/8" at 197' circulated with cement.

Circulated hole with heavy mud, set cementing plug at 200', displaced 20 sax cement through drill pipe, heavy mud to 180', set cementing plug, 1/2 sack hulls and 15 sax cement, heavy mud to 40', set cementing plug, 1/2 sack hulls and 10 sax cement to bottom cellar.

Very truly yours,

Signed: [Signature]  
Conservation Division Agent

RECORDED  
SERIALIZED  
12-2-58  
DEC 2 - 1958  
CONSERVATION DIVISION  
Wichita, Kansas