

State of Kansas



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN - 8 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Lattimer of Raymond Oil Company has this date requested permission to plug the following described well:

Mr. Lattimer guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Company

Complete Address: 410 4th Nat'l Bk. Bldg., Wichita, Ks.

Lease Name: Stephens "A" Well No. 1

Location: SE SW SW Sec. 27 Twp. 16 Rge. 20 (E)(W) X

County: Rush Total Depth 3927 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lattimer was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 510' and displace
100 sc cement thru drill pipe. Heavy mud to 210' set cementing plug and
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Geo. P. Massey
Conservation Division Agent